



FAPS

Prof. Dr.-Ing. Jörg Franke

**Institute for Factory Automation
and Production Systems**

Friedrich-Alexander University Erlangen-Nuremberg



**Friedrich-Alexander-Universität
Technische Fakultät**

Solutions for an automated production of WPT-Systems

CERV 2023

Maximilian Kneidl M.Sc.

Test tracks all over the world prove that the technology of wireless charging is feasible. The challenge for scaling up the technology is the automation of manufacturing processes.

ORNL (2016), Knoxville
10 m, 20 kW, $\eta = 90 \%$

IPT Tech. (2015), Mannheim
80 m, 200 kW

duraBast (2022)
Cologne, 100 m

KAIST OLEV (2010), Seoul
370 m, 100 kW, $\eta = 74 \%$

FABRIC (2017), Versailles
100 m, 20 kW, $\eta = 70 \%$

Electreon (2019)
Gotland, 1600 m; 70 kW

ASPIRE (2022)
Logan, 50 m

EnBW (2019)
Karlsruhe, 100 m

E|MPower (2024)
Bavaria, 1 km

Auckland (2013)
10 m, 30 kW, $\eta = 85 \%$

Labels in Electreon image: ABOVE-GROUND MANAGEMENT UNIT, UNDER-GROUND MANAGEMENT UNIT, UNDER-ROAD COIL SEGMENTS

The fully automated production and deployment of inductive power transfer systems is characterized by process-spanning challenges.


Winding

- Mechanical behaviour of litz-wires influences the winding process
- Mechanical stresses on primary insulation
- Lack of automated flat winding kinematics and tools
- Termination and bridging of litz-wire is depending on coil topology




Contacting

- Primary insulation influences the stripping process significantly
- Defects in the electrical joints influence the quality factor of the coil
- Mechanical connection must be ensured over the entire lifetime
- Combined stripping and contacting processes reduce manufacturing efforts




Potting

- Homogenous filler distribution is essential for heat transfer
- Dielectric properties ensure operation over lifetime
- Air traps and delamination increase the risk of partial discharges
- Compatibility to road construction technologies and materials




Deployment

- Mechanical stiffness of construction elements must be ensured
- Automatic deployment in accordance to modern road construction technologies
- Mobile contacting technologies




With data driven methods, flexible processes and improved quality control, FAPS investigates further advances manufacturing wireless power transfer systems.

Process chain of coil module manufacturing



Scalable integration of coil modules in infrastructure





FAPS

Prof. Dr.-Ing. Jörg Franke

**Institute for Factory Automation
and Production Systems**

Friedrich-Alexander University Erlangen-Nuremberg



**Friedrich-Alexander-Universität
Technische Fakultät**

Seamless
energy

**THANK
YOU**